

SCREEN PROCESS : m/706 "BOLT BINDS ON REC"

TO BE DONE BEFORE ASSY. OF FIRE CONTROL HOUSING.

INSERT MASTER BOLT ASSY. INTO RECEIVER;
CHECK DRAG OF FIRING PIN STRIKER WITH CLEARANCE
SLOT IN RECEIVER. ANY PARTS WITH INTERFERENCE
SHOULD BE SET ASIDE FOR REPAIR.

REC. THAT PASS TEST TO BE VISUALLY INSPECTED FOR
CENTRALITY OF FIRE CONTROL SLOT TO STRIKER
CLEARANCE SLOT, BY LOOKING AT RECEIVER
FROM BOTTOM SIDE. IF CENTRAL, FIRE CONTROL
TO BE ASSEMBLED THEN AGAIN TRY BOLT
FOR INTERFERENCE.

A. R. BASZCZUK
C. S. POORE

XL: G. J. HILL
M. HARDY
A. HUFFMAN
D. LONIS
J. KELLEY
J. BALIU
W. ACKLEY
J. P. LINDE
R. L. STAFFORD